BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2020-21/OW/WORK_INDENT41608

APPROVED SCHEDULE - B

.EE/BTP/BBMP/E-PMT/01/2020-21, Date: 05.05.2020

ıme of Work:Improvements to roads of shabarinagara & surrounding areas in ward no.07 yataranapura.

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of Abbu Sambasiva Reddy ( )	
				In Figures	In Words
1	2.7	Dismantling of existing structures like culverts,bridges, retaining walls and other structure comprising of masonry, cement concrete, wood work, steel work, including T&P and scaffolding wherever necessary, sorting the dismantled material, disposal of unserviceable material and stacking the serviceable material with all lifts complete as per specifications. B.Cement Concrete Grade M-15 & M-20.	Sqm	500.0	Rupees Five Hundred Only
2	277.85	Removing and refixing stone slabs of drains and pointing in CM(1:3)	Sqm	100.0	Rupees One Hundred Only
3	457.29	Earthwork excavation by manual means in rodinary soil involving an average horizontal throw upto 2 m and an average lift upto 1.5m, excavated surafce levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking clods complete as per specifications.	Cum	120.0	Rupees One Hundred Twenty Only
4	37.73	Providing and laying in position plain cement concrete of Mix 1:3:6 with OPC @ 220kgs, with 40mm and down size graded granite metal coarse aggregates @0.892cum and fine aggregates @ 0.465cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation including cost of all materials, labour, HOM curing complete as per specifications.	Cum	4500.0	Rupees Four Thousand Five Hundred Only
5	60.53	Providing and laying in position plain cement concrete of mix 1:2:4 with cement @ 240 kgs, with 20 mm and down size graded granite matel coarse aggregates @ 0.878 cum and fine aggragtes @ 0.53cum, machine mixed concrete laid in layers not eceeding 15 cms, thick well compacted, in foundation, plinth and cills including cost of all materials, labour HOM machinery curing complate as per specifications.	Cum	6000.0	Rupees Six Thousand Only
6	40.5	Providing and constructing granite /trap/basalt size stone masonry in foundation with cement mortar 1:6, stone hammered dressed in courses not less than 20cms hign, bond stones at two m apart in each course including cost of materials, labour, curing etc., complete as per specifications	Cum	4500.0	Rupees Four Thousand Five Hundred Only
7	90	Providing ruled pointing to coursed stone masonry with cement mortar 1:4, 20 mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing complete as per specifications cement mortar 1:4.	Sqm	150.0	Rupees One Hundred Fifty Only
8	3.33	Providing TMT Steel Reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications.	Tonne	69000.0	Rupees Sixty Nine Thousand Only
9	408	Providing and removing Centering, shuttering, strutting, propping etc., for columns, pillars, piers, abutments, post and struts, square / rectangular slabs /side walls polygon in plan including cost of materials, labour complete as per specification and directions of the Engineer in charge.	Sqm	400.0	Rupees Four Hundred Only
10	127.5	Providing granite slabs of selected quality roughly dressed and fixed in cement mortar (1:6) including fixing curing etc., complete10cms thick.	Sqm	1400.0	Rupees One Thousand Four Hundred Only
11	127.5	Providing one line dressing to granite stone slabs/granite stone masonry as per specifications.	Sqm	400.0	Rupees Four Hundred Only

Signature of the contractor

Executive Engineer

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of Abbu Sambasiva Reddy ( )	
				In Figures	In Words
12	130.75	Providing and fixing 10cms thick pre cast RCC covering slab using reinforced cement concrete M20 mix with stone aggregate 20mm and down size including centring shuttering reinforcement and bar bending machine mixed concrette laid in layers not exceeding 15 cm thick wellcompacted cost of all materials labour curing complete as per specfications (Data Rate Approved)	Sqm	1800.0	Rupees One Thousand Eight Hundred Only
13	144.9	Providing and fixing 20 cm thick pre cast RCC covering slab using reinforced cement concrete M 20 mix with stone aggregate 20 mm and down size including centring shuttering reinforcement and bar bending machine mixed concrete laid in layers not exceeding 15 cm thick wellcompacted cost of all materials labour curing comlete as per specification (Data Rate)	Sqm	4000.0	Rupees Four Thousand Only
14	457.29	Loading and unloading of stone boulder/stone aggregates/ sand/ kanker/ moorum. KSRRB M100-1:Placing tipper at loading point loading with front end loading, dumping turning for return trip, excluding time for haulage and return trip complete as per specification MORTH	Sqm	94.0	Rupees Ninety Four Only

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92
16/02

16/02